

## **Sound wall conflict with overhead electric**

Overhead utilities run over the project site. When sections of a high sound wall were hoisted into place, the boom on the crane was in conflict with the wires. The Contractor had to get the electric utility to shut off power to the lines while the erection was taking place. Include in the contract the deactivation and reactivation of the lines so the contractors bidding on the project can include it in their pricing.